IN PE: PETITION FOR ZONING VARIANCE NE/S Seneca Park Road 950 ft. SE c/l of Namette Lane * ZONING COMMISSIONER 821 Seneca Park Road * OF BALTIMORE COUNTY 15th Election District 5th Councilmanic District * Case No. 91-217-A Laura E. Earles, Legal Owner Wayne T. Danielek, Contract

Purchaser, Petitioner

* * * * * * * * * * FINDINGS OF FACT AND CONCLUSIONS OF LAW

The Petitioner herein request a zoning variance from Section 402 to permit a 50 ft. lot width, 5 ft. and 13 ft. sided yard setbacks, and an 18 ft. side yard setback sum in liev of 80 ft., 15 ft. and 35 ft. respectfully, as more particularly described on on Petitioner's Exhibit No. 1.

The Petitioner, Laura E. Earles, deceased, was represented by Gilbert Wagner, in his capacity as Personal Representative of her Estate. Mr. Wagner and the Estate was represented by Alfred L. Brennan, Jr., Esquire. Also appearing on behalf of the Petition was Jean Wagner. There were no Protestants.

Testimony indicated that the subject property known as 821 Seneca Park Road, consists of .508 acres +/-, zoned D.R.5.5, and is located within the Chesapeake Bay Critical Areas.

Mr. Wagner testified that the subject dwelling has existed in its current condition for approximately 25 to 30 years and that he personally assisted in its construction. Mr. Wagner testified that his Aunt, the deceased, Laura Earles, had resided there prior to her death. Mr. Wagner further testified that he has discussed this matter with the adjoining neighbors and they have no objection to the requested relief, as indicated by the signed affidavits marked Petitioner's Exhibits 5 and 6.

Mrs. Jean Wagner indicated that the subject lot was purchased in 1952 and that the existing dwelling was constructed in 1954.

After due consideration of the testimony and evidence presented, in the opinion of the Zoning Commissioner, the relief requested sufficiently complies with the requirements of Sections 307.1, 307.2 and 500.14 of the Baltimore County Zoning Regulations (B.C.Z.R.) and should therefore be granted. There is no evidence in the record that the subject variance would adversely affect the health, safety, and/or general welfare of the public. Furthermore, strict compliance with the B.C.Z.R. would result in practical difficulty and/or unreasonable hardship upon the Petitioner.

The facts and evidence presented tend to establish that special conditions or circumstances exist which are peculiar to the land or structures located within the Chesapeake Bay Critical Areas of Baltimore County; that to deny the relief requested would result in practical difficulty, unreasonable hardship, or severe economic hardship upon the Petitioner; and that strict compliance with the Chesapeake Bay Critical Area requirements and the B.C.Z.R. would deprive the Petitioner of rights commonly enjoyed by other properties in similar areas within the Chesapeake Bay Critical Areas in Baltimore County. The granting of the relief requested will not confer upon the Petitioner any special privilege that would be denied by the critical area regulations to other lands or structures within the Chesapeake Bay Critical Areas. Clearly, the request is not based upon conditions or circumstances which are the result of the Petitioner's actions, nor does the request arise from a condition relating to land or building use, either permitted or non-conforming, on another property. The relief requested is in harmony with the general spirit and intent of the Critical Areas legislation for Baltimore County and conforms to the requirements as set forth in Section 500.14 of the B.C.Z.R.

In accordance with Section 500.14 of the B.C.Z.R., the Director of the Department of Environmental Protection and Resource Management has submitted recommendations which describe what steps the Petitioner must take to insure that the relief requested complies with the following Chesapeake Bay Critical Areas requirements to:

> 1) Minimize adverse impacts on water quality that result from pollutants that are discharged from structures or conveyances or that have run off from surrounding lands;

2) Conserve fish, wildlife, and plant habitat; and

3) Be consistent with established land use policies for development in the Chesapeake Bay Critical Area which accommodate growth and also address the fact that, even if pollution is controlled, the number, movement, and activities of persons in that area can create adverse environmental impacts.

These recommendations shall be attached hereto and become a permanent part of the decision rendered in this case. There is no evidence in the record that the relief requested would adversely affect the health, safety, and/or general welfare of the public provided there is compliance with the requirements of the Department of Environmental Protection and Resource Management as more fully described below.

Pursuant to the advertisement, posting of the property, and public hearing on this Petition held, and for the reasons given above, the relief requested should be granted.

THEREFORE, IT IS ORDERED by the Zoning Commissioner for Baltimore County this 30 day of 124 mary, 1991 that the Petition for a Zoning Variance from Section 402 to permit a 50 ft. lot width, 5 ft. and 13 ft. side yard setbacks, and an 18 ft. side yard setback sum in lieu

of 80 ft., 15 ft. and 35 ft. respectfully, is hereby GRANTED, subject, however, to the following restriction which are conditions precedent the

> 1. The Petitioner is hereby made aware that proceeding at this time is at his own risk until such time as the 30 day appellate process from this Order has expired. If, for whatever reason, this Order is reversed, the Petitioner would be required to return, and be responsible for returning, said property to its original condition.

IT IS FURTHER ORDERED that the Petitioner shall comply fully and completely with all requirements and recommendations of the Department of Environmental Protection and Resource Management, as set forth in their comments dated February 1, 1991, attached hereto and made a part hereof.

> Zoning Commissioner for Baltimore County

cc: Peoples Counsel

relief granted herein:

PETITION FOR ZONING VARIANCE

TO THE ZONING COMMISSIONE. OF BALTIMORE COUNTY: 91-217-A The undersigned, legal owner(s) of the property situate in Baltimore County and which is described in the description and plat attached hereto and made a part hereof, hereby petition for a 402 to permit a 50 ft. lot width, 5 ft. and 13 ft. side yard setbacks, and an 18 ft. side yard setback sum in lieu of 80 ft. 15 ft. and 35 ft. respectively.

of the Zoning Regulations of Baltimore County, to the Zoning Law of Baltimore County; for the following reasons: (indicate hardship or practical difficulty)

SEE EXHIBIT "A" ATTACHED HERETO AND MADE A PART HEREOF.

Property is to be posted and advertised as prescribed by Zoning Regulations. I, or we, agree to pay expenses of above Variance advertising, posting, etc., upon filing of this petition, and further agree to and are to be bound by the zoning regulations and restrictions of

Baltimore County adopted pursuant to the Zoning Law For Baltimore County. I/We do solemnly declare and affirm, under the penalties of perjury, that I/we are the legal owner(s) of the property

| | which is the subject of this retition. | | |
|--|--|-------------------------|--|
| Contract Purchaser: | Legal Owner(s): | | |
| WAYNE T. DANIELAK (Type of Print Name) | LAURA E - EARLES (Type or Print Name) | 1043 NE 34
F-3 | |
| Mayo Cancelo Signature | Vauro E. Garles. Signature | D.T. 12-0-91 | |
| 7313 CONLEY STREET Address | (Type or Print Name) | 200 | |
| BALTIMORE, MD 21224 City and State | Signature | DP _G | |
| Attorney for Petitioner: | 110 A Greenword Creek | R.Q. | |
| (Type or Print Name) | Address Queenstown MD 21658 City and State | | |
| Signature | Name, address and phone number of legal tract purchaser or representative to be co | owner, con-
ontacted | |
| Address | TERI PASCUAL | | |
| City and State | Name | | |
| Attorney's Telephone No.: | Address | L)_288=1700
hone No. | |
| ORDERED By The Zoning Commissioner of Baltimore County, this day | | | |
| of, 19, that the subject matter of this petition be advertised, as required by the Zoning Law of Baltimore County, in two newspapers of general circulation throughout Baltimore County, that property be posted, and that the public hearing be had before the Zoning out Baltimore County in Room 106, County Office Building in Towson, Baltimore County, on the day of, 19, at o'clock | | | |
| County, on theM. | 1 Robert Ha | , | |

Robert fraince

SUBJECT PROPERTY HISTORY:

CONTRAL A TO 91-217-A

Lot # 124 was purchased in 1952 by Kermit & Laura E. Earles. The main structure of the dwelling was built in 1954. According to Affidavits from the neighbors and information from the surviving owner Laura Earles, a permit was issued to construct an addition on the subject property in 1966 or there about. The dwelling has since been used as a two unit and assessed for tax purposes as a two unit. Tax assessment records refer back as far as 1975.

Buyer and Seler are unable to purchase additional land from owners on either side of Lot #124 to meet the minimum required 80 feet width of the front building line.

Critical Arth

220

91-217-A

ZONING DESCRIPTION

BEING KNOWN AND DESIGNATED AS LOT NO. 124 FRONTING ON HUGHES BOULEVARD, AS SHOWN ON THE REVISED PLAT OF SENECA PARK BEACH, WHICH PLAT IS RECORDED AMONG THE LAND RECORDS OF BALTIMORE COUNTY IN PLAT BOOK NO. 8, FOLIO 45, TOGETHER WITH THE RIGHT TO USE OF SAID LAND AND ALL ROADS CONNECTING THEREWITH IN COMMON WITH OTHERS AND ALSO ALL PARKS AND BEACHES IN SAID SENECA PARK LAID DOWN FOR COMMON USE. THE IMPROVEMENTS THEREON BEING KNOWN AS 821 SENECA PARK ROAD, AND LOCATED IN THE #15 ELECTION DISTRICT, AND CONTAINING 22,150 SQUARE FEET.

CERTIFICATE OF POSTING ZONING DEPARTMENT OF BALTIMORE COUNTY Towsen, Maryland

| District /500 Posted for: / bylancs | Date of Posting 1/14/9/ |
|--|-------------------------------------|
| District | Late of Footingy |
| Posted for: | |
| Petitioner: Laure F. Corles T | Wayne 1. Danielel |
| Petitioner: Laure F. Forles & Location of property: NEIS Someca | POX Rd 930' SE/NameTITY FOND |
| 1 H Sonoco Pt. Rd | , |
| Location of Signs Focing Sonocof | Porto Rt. approx, 15 Fr. 100 6 way. |
| on property of fetitioners | |
| 7 | 1.—10. |
| Posted by Military Signature | Date of return: 1/18/9/ |
| Kumber of Signs: | ŕ |

CERTIFICATE OF PUBLICATION

NOTICE OF HEARING The Zoning Commissioner of Battimore County, by authority of the Zoning Act and Regulations of Battimore County will hold a public hearing on the property identified herein in Room 106 of the County Office Building, located at 111 W. Chesapeake Avenue in Towson, Maryland 21204 se follows: Petition for Zoning Variance Case number: 91-217-A NE/S Seneca Park Road, 950' SE of c/l of oth Councilmanic Legal Owner(s): Laura E. Earles Contract Purchaser(s): Wayne T. Danielak Hearing Date: Wednesday, Jan. 30, 1991 at 11:00 a.m. Variance: to permit a 50 ft. lot width, 5 ft. and 13 ft. side yard etbacks, and an 18 ft side yard etback sum in lieu of 80 ft., 15 ft.,

J. ROBERT HAINES

THIS IS TO CERTIFY, that the annexed advertisement was published in THE JEFFERSONIAN, a weekly newspaper published in Towson, Baltimore County, Md., once in each of _

5. Refe Alm

\$ 37.52

altimore County Government Zoning Commissioner Office of Planning and Zoning

February 21, 1991

111 West Chesapeake Avenue Towson, MD 21204

Alfred L. Brennan, Jr., Esquire 825 Eastern Boulevard Baltimore, Maryland 21221

Mr. Wayne T. Danielak 7313 Conley Street Baltimore, Maryland 21224

> RE: Petition for Zoning Variance Case No. 91-217-A Wayne T. Danielak, Contract Purchaser Laura E. Earles, Legal Owner

Enclosed please find the decision rendered in the above captioned case. The Petition for Zoning Variance has been granted in accordance with the attached Order.

In the event the decision rendered is unfavorable to any party, please be advised that any party may file an appeal within thirty (30) days of the date of the Order to the County Board of Appeals. If you require additional information concerning filing an appeal, please feel free to contact our Appeals Clerk at 887-3391.

Very truly yours,


J. Robert Haines
Zoning Commissioner


887-3353


cc: Peoples Counsel

mik - 11/21/10 acail anytime est. time = = hro-less

weeks, the first publication appearing on /-3, 199/2.








Enclosed are all comments submitted from the members of the Committee at this time that offer or request information on your petition. If similar comments from the remaining members are received, I will forward them to you. Otherwise, any comment that is not informative will be placed in the hearing file. This petition was accepted for filing on the date of the enclosed filing certificate and a hearing scheduled accordingly.

IT NOULD BE APPRECIATED IF YOU WOULD RETURN YOUR WRITTEN COMMENTS TO MY OFFICE, ATTENTION JULIE WINIARSKI. IF YOU HAVE ANY QUESTIONS REGARDING THIS, PLEASE CONTACT HER AT 887-3391.

Zoning Plans Advisory Committee

cc: Mr. Wayne T. Danielak 7313 Conley Street Baltimore, MD 21224



Baltimore County Government
Zoning Commission

111 West Chesapeake Avenue

Towson, MD 21204

Office of Planning and Zoning

Your petition has been received and accepted for filing this

ZONING COMMISSIONER

Received By:


19th day of December, 1990.

Petitioner: Laura E. Earles


Petitioner's Attorney:


Zening Commissioner


887-3353



Baltimore County Government Zoning Commissioner








401 Bosley Avenue Suite 405

Baltimore County Government

887-3353

Zoning Commissioner

Office of Planning and Zoning



887-3554

Fax 887-5781

Baltimore County Government

Department of Public Works

Bureau of Traffic Engineering

Baltimore County Fire Department 700 East Joppa Road, Suite 901 Towson, Maryland 21204-5500 (301) 887-4500

Paul H. Reincke

DECEMBER 13, 1990

. J. Robert Haines Zoning Commissioner Office of Planning and Zoning Baltimore County Office Building Towson, MD 21204

Dennis F. Rasmussen

LAURA E. EARLES RE: Property Owner:

#821 SENECA PARK ROAD

Location: Zoning Agenda: DECEMBER 18, 1990 Item No.:

Gentlemen:

Pursuant to your request, the referenced property has been surveyed by this Bureau and the comments below are applicable and required to be corrected or incorporated into the final plans for the property.

7. The Fire Prevention Bureau has no comments at this time.

Fire Prevention Bureau Special Inspection Division

JK/KEK

BALTIMORE COUNTY, MARYLAND DEPARTMENT OF ENVIRONMENTAL PROTECTION AND RESOURCE MANAGEMENT

DATE: February 1, 1991

ZONING OFFICE

INTER-OFFICE CORRESPONDENCE

TO: Mr. J. Robert Haines Zoning Commissioner

FROM: Mr. Donald C. Outen

SUBJECT: Petition for Zoning Variance - Item 220 Earles Property Chesapeake Bay Critical Area Findings

SITE LOCATION The subject property is located at 821 Seneca Park Road. The site is within the Chesapeake Bay Critical Area and is classified as a Limited Development Area (LDA).

APPLICANT'S NAME Ms. Laura E. Earles

APPLICANT PROPOSAL

The applicant has requested a variance from section 402 of the Baltimore County Zoning Regulations to permit a "50 foot lot width, 5 foot and 13 foot side yard setbacks, and an 18 foot side yard setback sum in lieu of 80 feet, 15 feet, and 35 feet respectively".

GOALS OF THE CHESAPEAKE BAY CRITICAL AREA PROGRAM

In accordance with the Chesapeake Bay Critical Area Program, all project approvals shall be based on a finding which assures that proposed projects are consistent with the following goals of the

- 1. "Minimize adverse impacts on water quality that result from pollutants that are discharged from structures or conveyances or that have runoff from surrounding lands;
- Conserve fish, wildlife and plant habitat; and
- Establish land use policies for development in the Chesapeake Bay Critical Area which accommodate growth and also address the fact that even if pollution is controlled, the number, movement, and activities of persons in that area can create adverse environmental impacts." <COMAR 14.15.10.01.0>

BALTIMORE COUNTY. MARYLAND

INTER-OFFICE CORRESPONDENCE DECEMEBER 11, 1990

J. ROBERT HAINES, ZONING COMMISSIONER, DEPARTMENT ZONING CHARLES E. BURNHAM, PLANS REVIEW CHIEF, DEPARTMENT OF

PERMITS & LICENSES

SUBJECT:

ZONING ITEM #: 220 PROPERTY OWNER: Legal Owner: Laura E. Earles Contract Purchaser: Wayne T. Danielak LOCATION: NE/S Seneca Park Road, 950' SE of centerline Nannette Laue (#821 Seneca Park Road) ELECTION DISTRICT: 15th COUNCILMANIC DISTRICT: 5th

A REVIEW OF THE SITE PLAN FOR THE ABOVE ZONING ITEM INDICATES THE FOLLOWING:

() PROPOSED SITE PLAN DOES, DOES NOT, COMPLY TO STATE CODE OF MARYLAND REGULATION 05.01.07, MARYLAND BUILDING CODE FOR THE

() PARKING LOCATION () NUMBER PARKING SPACES () BUILDING ACCESS

HANDICAPPED.

() RAMPS (degree slope) () CURB CUTS () SIGNAGE

() PLAN DOES, DOES NOT COMPLY TO SET BACKS FOR EXTERIOR FIRE SEPARATION DISTANCE OF ARTICLE 5 AND ARTICLE 9 OF THE CURRENT BALTIMORE COUNTY BUILDING CODE.

(X) A BUILDING PERMIT IS REQUIRED BEFORE ANY CONSTRUCTION CAN BEGIN. SECTION 111.1 OF ARTICLE 1. CONSTRUCTION DRAWINGS REQUIRED.

() A CHANGE OF OCCUPANCY PERMIT IS REQUIRED TO CHANGE THE EXISTING USE OF THE STRUCTURE TO THE PROPOSED USE. SEE ARTICLE THREE AND ARTICLE ONE, SECTION 103.2 ALTERATIONS MAY BE NECESSARY BY CODE TO COMPLY TO NEW USE REQUIREMENTS.

STRUCTURE IS SUBJECT TO FLOOD PLAIN LIMITATIONS, SECTION 516.0 COUNCIL BILL #158-88 (BALTIMORE COUNTY BUILDING CODE). VERIEY ELEVATION WILL COMPLY TO SECTION SILIO WHEN Filing Permit () OTHER -

PERMITS MAY BE APPLIED FOR @ ROOM 100, 111 WEST CHESAPEAKE AVENUE, TOWSON, MARYLAND 21204 - PHONE - 887-3900.

THIS REVIEW COVERS ONLY MAJOR ITEMS ASSOCIATED WITH THE SITE PLAN, A FULL REVIEW MAY BE CONDUCTED WHEN THE PERMIT APPLICATION AND PLANS ARE SUBMITTED.

APPLICABLE CODE: 1987 NATIONAL BUILDING CODES AS ADOPTED BY COUNCIL BILL #158-88

Memo to Mr. J. Robert Haines February 1, 1991

REGULATIONS AND FINDINGS

Regulation: "A minimum 100 foot buffer shall be established landward from the mean high water line of tidal waters, tidal wetlands, and tributary streams" <Baltimore County Code Sec. 22-216(a)>.

Finding: This property is located approximately 300 feet from the tidal waters of Seneca Creek, therefore, no disturbance of the shoreline buffer shall occur.

2. Regulation: "No dredging, filling, or construction in any wetland shall be permitted. Any wetland must be adequately protected from contamination" <Baltimore County Code Sec. 22-98>

Finding: No wetlands were found within the vicinity of this house, therefore, no filling of wetlands shall occur.

3. Regulation: "The sum of all man-made impervious areas shall not exceed 15% of the lot" <COMAR 14.15.02.04 C.(7)>. Finding: No construction is proposed in conjunction with this

variance request. However, any future development shall not be allowed to increase impervious surfaces above 15% of the lot. 4. Regulation: "If no forest is established on proposed development sites, these sites shall be planted to provide a

forest or developed woodland of at least 15%" <COMAR 14.15. 02.04 C.(5)>. Finding: This property presently contains forest cover of at least 15%. However, additional tree planting is beneficial. Trees are an important factor in improving water quality. The roots of trees greatly improve the infiltration rate of storm water and efficiently remove nitrogen from subsurface flows of

groundwater. Trees also act as both a barrier and a sponge, blocking and absorbing eroding soils and the phosphorous associated with them. <u>5. Regulation:</u> "The stormwater management system shall be designed so that:

(1) Development will not cause downstream property, watercourses, channels or conduits to receive stormwater runoff at a higher rate than would have resulted from a ten year frequency storm if the land had remained in its predevelopment state;

Memo to J. Robert Haines

February 1, 1991

Page 3

(2) Infiltration of water is maximized throughout the site,

rather than directing flow to single discharge points; and (3) Storm drain discharge points are decentralized to simulate the predevelopment hydrologic regime.

(4) There is sufficient storage capacity to achieve water quality goals of COMAR 14.15 and to eliminate all runoff caused by the development in excess of that which would have come from the site if it were in its predevelopment state" <Baltimore County Code, Section 22-217(h)>.

Findings: The runoff from this house is presently directed through downspouts and into two drainage trenches. This complies with the above regulations since it maximizes the infiltration of stormwater.

CONCLUSION

The Zoning Variance shall be conditioned so the project proposal is in compliance with the Chesapeake Bay Critical Area Regulations and Findings listed above. This project is in compliance with Chesapeake Bay Critical Area Regulations, and is therefore approved. If there are any questions, please contact Mr. David C. Flowers at 887-2904.

> Department of Environmental Protection and Resource Management

DCO:DCF:ju Attachment

cc: The Honorable Ronald B. Hickernell The Honorable Vincent Gardina The Honorable Donald Mason Mrs. Janice B. Outen

PARTITODE COURTS, HALVIAND THEROFFICE COPPESSOUDENCE

To: Zoning Advisory Committee PATE: December 8, 1990 FROM: Robert W. Roulling, P.F.

The Davelorers Engineering Districted has reviewed the subject sening items and me have no comments for

BE: A wind Advisory Committee Me sting

for Desambles 18, 1999

Items 216, 217, 218, 220, 223 and 209,

For Item 207, a County Daylow deg on Mosting is required.

For Item 228, the previous County Deview Group comments Robert Barling

POPMET M. POWERIG, T. Chief

Developen Eprinscript Division

RWB:s

EFFECTIVE: January 29, 198

20.19895ETTICK: 516.0 A Section added to read as follows:

516.1 ARMAS SUBJECT TO INUNDATION BY TIDEWATERS:

Whenever building or additions are constructed in areas

Areas beneath buildings will not be considered as basements if

Exception: Residential Storage Buildings 300 square feet or Less.

Crawl spaces under buildings constructed in the tidal plain,

New or replacement utility systems, including but not limited

516.2 RIVERINE AREAS SUBJECT TO INUNDATION BY SURFACE WATERS WITHIN

No structures or additions shall be within the 100-year flood

Exception: Buildings in areas designated as "TRINGE" areas by the

Reconstruction of residential dwelling units shall be governed

Reconstruction of other than residential buildings or

subject to inundation by tidewaters, the building's lowest floor (including

bassament) small be not lower than one (1) foot above the 100-year flood

elevation, as established by the U.S. Army Corps of Engineers or the Federal

Flood Insurance Study, whichever is more restrictive. These buildings or

additions shall be designed and adequately anchored to prevent flocation,

collapse, or lateral movement of the structure with materials resistant to

headroom to underside of floor joists is less than six feet or if

as determined by the U.S. Army Corp of Engineers or the Federal Flood

Insurance Study, whichever is more restrictive, shall be constructed so that

water will pass through without resulting debris causing damage to the

to water supply, sanitary sewage, electric gas and oil, must be designed to

minimize or eliminate infiltration of flood waters into the systems and

discharges from the systems into flood waters, and require on-site waste

disposal systems to be located so as to avoid impairment of them or

plain of any watercourse. The 100-year flood plain shall be based upon the

Federal Flood Insurance Study or the Department of Public Works, whichever

is the more restrictive. This determination shall include planned future

by Sections 103.0 or 120.0 as applicable, except that rebuilding of

residential dwelling units damaged in excess of 50 percent of physical value

shall also be governed by the provisions of Subsection 516.1 of this Section.

structures in the riverine areas shall be made to conform to 516.1 when

- TSECTION: 518.0 ----COMMUNICATION IN AREAS_SUBJECT TO FLOCKING

enclosure wails are at least 50 percent open.

contamination from them during flooding.

development of the watershed area.

damage exceeds 50 percent of physical value.

improvements of any property.

THE 100 YEAR FLOOD PLAIN!

Department of Public Works.

January 1989

(lood damaçe.

Baltimore County Government Zoning Commissioner Office of Planning and Zoning

111 West Chesapeake Avenue Towson, MD 21204

December 14, 1990

Terri Pascual Coldwell Banker 1205 Merritt Blvd. Baltimore, Maryland 21222

Re: Item #220 821 Seneca Park Road Petition for Zoning Variance

Dear Ms. Pascual:

Your letter requesting an early hearing with regard to the above captioned matter has been forwarded to me for reply.

Please be advised that it my job to schedule the zoning hearings and I am currently working with the second week of February, 1991. I am looking at the feasibility of slipping this matter into the January docket. To do so, someone must request postponement or withdrawal of their scheduled hearing.

If these circumstances come about, I will contact you again, either in letter form or with a notice of hearing.

Also I must inform you that even if we are able to get the hearing in during January, an Order cannot be written until all Critical Area requirements are meet. I suggest that you contact your client and ascertain that he is working with Mr. Flowers of DEPRM to avoid further delay of the final disposition of this matter.

Very truly yours,

G. G. Stephens

A MEMBER OF THE SEARS FINANCIAL NETWORK

Mr. Robert Haines Zoning Commissioner 111 West Chesapeake Avenue Towson, Maryland 21204

ZOWNE OFFICE

RE: Petition for Side Setback Variances 821 Seneca Park Road Baltimore, Maryland 21220

COLDWELL BANKER

RÉSIDENTIAL REAL ESTATE

Dear Mr. Haines,

A petition for side setback variances for the above mentioned property was filed November 21, 1990. We were instructed that the time period until the formal hearing would be three months.

This property is presently under contract of sale pending the approval of the variance. Unfortunately, the Federal Housing approval of the variance. Unfortunately, the redefal housing Administration is in the process of changing their mortgage insurance policy. Effective February 4, 1990, FHA will be requiring a larger down payment or premium payment. The buyer, Wayne Danielak, has neither the extra funds to meet the requirement nor does he qualify for the home with a larger mortgage insurance payment.

We understand that the Zoning Commission has set standards and regulations for a petition, but the time frame of three months would cause our contract of sale to become null and void.

As explained in the petition, 821 Seneca Park Road has existed as a two apartment dwelling for more than 25 years. We have contacted several of the neighbors and even have signed affidavits indicating their knowledge of the two units.

Time is our strongest barrier to the solution of this situation. All parties concerned would appreciate any consideration from you or your staff. Thank you in advance for your time.

Sincerely, Don Pascual Teri Pascual Coldwell Banker

SUBJECT PROPERTY:

LOT # 124 LAURA E. EARLES 821 SENECA PARK ROAD 50 X 443 2195/287

LOT # 122-123 GEORGE H. & DORIS BUSICK 815 SENECA PARK ROAD 100 X 221.5 4379/0161

LOT # 122-123 DORA A. OWENS 817 NANNETTE LANE 100 X 220.35 5067/024

5930/0625

LOT # 125 ROBERT H. & EVELYN L. MCINTOSH 823 SENECA PARK ROAD 50×443

Subject Property is located in a Critical Bay Area. Flood Plan: A10 Elevation: EL10

CRITICAL AREA

date:11-9-90


prepared by:


91-217-A 220


Plat to accompany Petition for Zoning XX Variance Special Hearing PROPERTY ADDRESS: 821 SENECA PARK ROAD see pages 5 & 6 of the CHECKLIST for additional required information Subdivision name: SENECA PARK BEACH LAURA E. EARLES Subsect Protectly ----Vicinity Map scale: 1"-1000" LOCATION INFORMATION Councilmanic District: 5 Election District: 15 1"=200" scale map#: NE-3L Zonlng: ()25,5 Lot size: 508 22,150 ncrenge square feet SEWER: 🔲 🗓 WATER: 🖺 🔲 Chesupenke Bay Critical Area: X Prior Zoning Hearings: NONE CRITICAL AREA Zoning Office USE ONLY!


Scale of Drawing: 1" = 60"

reviewed by: ITEM #: CASE#:










I hereby affirm that I live next door to the two apartment dwelling known as 821 Seneca Park Road, 21220. I understand that the owner of the property has requested a Variance for a side-yard set back of 50' in lieu of the required 80'. I have no objection to the granting of this Variance.

STATE OF MARYLAND, COUNTY OF BALTIMORE, to wit:

and facts hereinabove set forth are true to the best of his/her knowledge

AS WITNESS my hand and Notarial Seal.



PETITIONER'S EXHIBIT 5

91-217A

